

M

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 10 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Bovaird Supply Company

Complete Address Box 2590 Tulsa, Oklahoma 74101

Lease Name Haney (SWD) Well No. 1

Location NW SW NW Sec. 13 Twp. 21 Rge. (E) (W) 16

County Pawnee Total Depth 3880'

Abandoned Oil Well Gas Well Input Well SWD Well XXX D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas License No. 399

Operation Completed: Hour 4P Day 8 Month 9 Year 1969

The above well was plugged as follows:

Total Depth 3880' 8 5/8 csg set at 972' cwc 475 sk.

5 1/2 csg set at 3880' cw 125 sk cmt.

Filled 5 1/2 csg W/sd (3800-3880) Dumped 5 sk cmt W/dump bailer. (3760-3800)

Cutoff and recovered 2905' of 5 1/2 csg.

Mud to 400' set rock bridge (375-400)

Dumped 5 yds readymix cement (0-375)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/10/69

INV. NO. 446-u

Signed: Leo F. Massey
Well Plugging Supervisor