

State of Kansas



FORM - CP-2
Rev. 9-8-64

15.159.30163.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

December 6, 1965

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

DEC - 9 1965

CONSERVATION DIVISION
WICHITA, KANSAS

Dear Sir:

Mr. Jim Lahar of Glickman Oil Company has this

date requested permission to plug the following described well:

Mr. Lahar guarantees payment of the plugging fee.

Operator's full Name: Glickman Oil Company

Complete Address: 702 South St. Francis, Wichita, Kansas

Lease Name: Rick Well No. 4

Location: Approx. 100' E of SW SE Sec. 17 Twp. 20 Rge. 10 (E) (W) X

County Rice Total Depth 3248' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole


Mr. Lahar was instructed to plug the well as follows:

Fill hole with mud to 210'. Push plug and 1/2 sack hulls to 210' and cement hole with 30 sacks through drill pipe.

Fill hole with mud to 35'. Push plug and 1/2 sack hulls to 35' and cap hole with 15 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,


Conservation Division Agent