

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

January 28, 1964

RECEIVED  
STATE CORPORATION COMMISSION

FEB 3 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Duke Burt of Burt Drilling Co. has this

date requested permission to plug the following described well:

Mr. Burt guarantees payment of the plugging fee.

Operator's full Name: Giles & Ollson & High Plains Production Co.

Complete Address: 353 Armour, Wichita, Kansas

Lease Name: Poncin Well No. 1

Location: NE NW NE Sec. 17 Twp. 20 Rge. 10 (E) (W) X

County Rice Total Depth 3407' Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Burt was instructed to plug the well as follows:

Fill hole with mud to 210'. Push plug and 1/2 sack hulls

to 210' and cement hole with 20 sacks through drill pipe.

Fill hole with mud to 40'. Push plug and 1/4 sack hulls to

40' and cap hole with 10 sacks cement.

Bridge rathole, and cement with 2 sacks.

Very truly yours,