



15.159.03878.0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

December 31, 1965

**RECEIVED**  
STATE CORPORATION COMMISSION

JAN 10 1966

CONSERVATION DIVISION  
WICHITA, KANSAS

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Sohio Petroleum Company

Complete Address: P.O. Box 673, Russell, Kansas

Lease Name: Mantel Well No. 4

Location: C N/2 SE NE Sec. 18 Twp. 20 Rge. 10 W X

County Rice Total Depth 3332' Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3310' and cement with 5 sacks.

Fill hole with mud to 200'. Set rock bridge from 200' to

190' and cement hole with 20 sacks. Fill hole with mud to

40'. Set rock bridge from 40' to 30' and cap hole with 10

sacks cement.

Very truly yours,

Conservation Division Agent