

State of Kansas



FORM - CP-2
Rev. 9-8-64

15.159.04716.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JOHN C. WOELK Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

January 5, 1966

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 11 1966

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co has this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Sohio Petroleum Company

Complete Address: P.O. Box 673, Russell, Kansas

Lease Name: Mantel Well No. 1

Location: SW SE NE Sec. 18 Twp. 20 Rge. 10 (E) (W) X

County Rice Total Depth 3299' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3270' and cement with 6 sacks.

Fill hole with mud to 200'. Set rock bridge from 200' to

190' and cement hole with 25 sacks. Fill hole with mud to

30'. Set rock bridge from 30' to 20' and cap hole with 10

sacks cement.

Very truly yours,

Conservation Division Agent