



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

August 15, 1963

RECEIVED  
STATE CORPORATION COMMISSION

AUG 19 1963

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Earl Morgan of Sholom Drlg. Co., Inc. has this

date requested permission to plug the following described well:

Mr. Morgan guarantees payment of the plugging fee.

Operator's full Name: Icer Addis

Complete Address: Box 519, Great Bend, Kansas

Lease Name: Kliele Well No. 4

Location: NW NW NE Sec. 8 Twp. 20 Rge. 10 (E) (W) X

County Rice Total Depth 3421 Oil Well

Gas Well    Input Well    SWD Well    D & A X Lost Hole   

Mr. Morgan was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 200'. Push  
plug and 1/2 sack hulls to 200' and cement with 20 sacks  
through drill pipe. Fill hole with mud to 35'. Push  
plug and 1/2 sack hulls to 35' and cap hole with 10 sacks  
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

  
 Conservation Division Agent