

State of Kansas



15.159.02738.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

December 31, 1967

RECEIVED
JAN 17 1967
CONSERVATION DIVISION
WICHITA, KANSAS
STATE CORPORATION COMMISSION

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ralph Lynch of Lynch Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Lynch guarantees payment of the plugging fee.

Operator's full Name: Specter Pipe & Supply, Inc.

Complete Address: P.O. Box 169, Russell, Kansas

Lease Name: Schloctermeier Well No. 1

Location: NE NW SE Sec. 8 Twp. 20 Rge. 10 (E) (W) X

County Rice Total Depth 3396' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Lynch was instructed to plug the well as follows:

Push 5 1/2" plug to 3085'. Fill hole with sand to 3075' and cement with 5 sacks. Fill hole with mud to 205'. Set rock bridge from 205' to 195' and cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent