

TO:
 STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 266 N. Main St., Ste. 220
 Wichita, KS 67202-1513

API Well Number: 15-115-19026-00-00
 Spot: NWSWNWNW Sec/Twnshp/Rge: 34-18S-2E
4373 feet from S Section Line, 5265 feet from E Section Line
 Lease Name: SCULLY A Well #: 4-34
 County: MARION Total Vertical Depth: 2930 feet

Operator License No.: 5399
 Op Name: TREK AEC, LLC
 Address: 200 W DOUGLAS, SUITE 101
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
II	5.5	2912		
PROD	5	2912		0 SX
SURF	8	157		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/19/2018 4:30 PM
 Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
 Proposal Rcvd. from: TANNER NELSON Company: _____ Phone: (620) 755-2571

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
 Date/Time Plugging Completed: 04/19/2018 4:30 AM KCC Agent: JERRY SPARLING

Actual Plugging Report:

RAN BAILER IN AND TAGGED BOTTOM @ 2930'. SANDED OFF BOTTOM TO 2880' CAPPED SAND WITH 5 SX COMMON CEMENT. RAN 180' OF 1" DOWN BACKSIDE TAGGED CEMENT AT 170'. REMOVED ONE JOINT TO 150'. RAN 250' 2 7/8" TUBING IN PRODUCTION CASING. QES RIGGED UP AND PUMPED 50 SX OF 60/40 POZMIX CEMENT WITH 4% GEL AND 2% CALCIUM CHLORIDE AND CIRCULATED TO SURFACE. THEN HOOKED UP TO 1" IN BACKSIDE AND PUMPED 170 SX 60/40 POZMIX CEMENT AND CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2880	2930	CSG	

AUG 2 2 2018
 INVOICED

Remarks: QES TICKET #54481. 220 SX 60/40 POZMIX 4% GEL & 2% CC.

Plugged through: CSG

District: 02

Signed _____

(Handwritten Signature)
 (TECHNICIAN)

(Handwritten mark)