

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-19923-00-00  
Spot: NESENESW Sec/Twnshp/Rge: 22-23S-13E  
1760 feet from S Section Line, 2900 feet from E Section Line  
Lease Name: LOVETT Well #: 1 OLD  
County: GREENWOOD Total Vertical Depth: 1587 feet

Operator License No.: 32044  
Op Name: TRIMBLE & MACLASKEY OIL LLC  
Address: 110 SOUTH ST PO BOX 171  
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6.625	1587		0 SX
SURF	8	1416		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/06/2018 12:00 PM  
Plug Co. License No.: 32044 Plug Co. Name: TRIMBLE & MACLASKEY OIL LLC  
Proposal Revd. from: TRIMBLE & MACLASKEY Company: \_\_\_\_\_ Phone: (620) 836-2000

Proposed Plugging Method: Cement plug on bottom Perf at 850 and 250 ft Cement plug at 850 Cement Plug at 250 ft to surface

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/06/2018 4:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

Ran tubing to 1560', pumped 30 sxs cement, pulled tubing to 846', pumped 30 sxs cement, pulled tubing to 250', pumped 170 sxs cement to surface, gel spacers between cement plugs.

**INVOICED**  
**AUG 23 2018**

RECEIVED  
KCC DIST # 3  
JUL 09 2018  
CHANUTE, KS

*MH*

Remarks:

Plugged through: TBG

District: 03

Signed *Michael Heffern*  
(TECHNICIAN)

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



15-073-19923

Cement or Acid Field Report  
 Ticket No. 4023  
 Foreman Russell Mcloy  
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
7-6-18	1000	Lovett #1 oild well	22	23	13	G.W.	Ks
Customer		Safety Meeting Rm AM JASON	Unit #	Driver	Unit #	Driver	
Mailing Address			104	ALAN M			
City		State	Zip Code				
Gribley		Ks	66852				

Job Type Plug oild well Hole Depth \_\_\_\_\_ Slurry Vol. \_\_\_\_\_ Tubing 2 3/8  
 Casing Depth 1587 Hole Size UNKNOWN Slurry Wt. \_\_\_\_\_ Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. N.A. Cement Left In Casing \_\_\_\_\_ Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: Safety meeting + Job Procedure

SPOT 30 SKs @ 1560  
 SPOT 30 SKs @ 846  
 SPOT 170 SKs 250' to surface  
 230 SKs TOTAL

NOTE Gel spacer Between plugs

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-105	1	Pump Charge	750.00	750.00
C-107	30	Mileage	3.95	118.50
C-203	230	SKs 60/40 Permox	12.75	2932.50
C-206	800#	Gel = 4%	.20	160.00
C-206	500#	Gel SPACER	.20	100.00
C-204	40#	Hulls	.45	18.00
C-205	50#	cracke } mixed in Bottom plugs	.60	30.00
C-10AB	9.89 Ton	Ton Mileage x 30 miles	1.35	400.55
			SUB TOTAL	4509.55
			5% Sales Tax	225.48
Authorization <u>Witnessed by Jim Thwaitte Co/R&amp;P</u>			Total	4605.38

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.