

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-23851-00-00  
Spot: SENENWNE Sec/Twnshp/Rge: 10-31S-13W  
4879 feet from S Section Line, 1563 feet from E Section Line  
Lease Name: CENTRAL MADDIX TRUST Well #: 1-10  
County: BARBER Total Vertical Depth: 4500 feet

Operator License No.: 5822  
Op Name: VAL ENERGY, INC.  
Address: 125 N MARKET ST STE 1110  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4300		WITH 2 SX CMT
PROD	5.5	4485	3000	WITH 125 SX CMT
SURF	8.625	221		WITH 190 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/16/2018 2:30 PM  
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.  
Proposal Revd. from: DEON HOWARD Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: SET CIBP @ 4300' & 2 SX CMT. PLUG AT 650' WITH 10 SX GEL & 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/16/2018 3:45 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4300' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 630' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 250' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT. TOP OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4364	4384		

INVOICED

AUG 27 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE & CEMENTING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
AUG 20 2018  
KCC DODGE CITY