

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-007-23519-00-00  
Spot: NENENW Sec/Twnshp/Rge: 34-34S-10W  
5010 feet from S Section Line, 3052 feet from E Section Line  
Lease Name: DALE Well #: 1  
County: BARBER Total Vertical Depth: 5383 feet

Operator License No.: 33235  
Op Name: CHIEFTAIN OIL CO., INC.  
Address: 101 S. 5TH ST. PO BOX 124  
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4380		WITH 2 SX CMT
PROD	5.5	5377	3000	WITH 200 SX CMT
SURF	8.625	332		WITH 275 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/17/2018 9:00 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Revd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4380' & 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/17/2018 10:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

\*\*TBG ANCHOR CATCHER WAS HUNG UP IN HOLE. UNABLE TO GET FREE. CUT TBG OFF ABOVE ANCHOR AT 4400'. TOC BEHIND 5 1/2" CASING IS AT 4280'.\*\*SET CIBP @ 4380' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 608' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 352' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4708	4714		

INVOICED

AUG 27 2018

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE & CEMENTING.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
AUG 20 2018  
KCC DODGE CITY