

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-13257-00-00
Spot: NWSESE Sec/Twnshp/Rge: 12-21S-13W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: BATMAN LINA Well #: 1
County: STAFFORD Total Vertical Depth: 3506 feet

Operator License No.: 31647
Op Name: CHURCHILL, KIM DBA K.C. OPERATIO
Address: 534 SE 70 AVE
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3496	1600	WITH 125 SX CMT
SURF	8.625	222		WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/15/2018 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: FELIX Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK TO 3210' WITH 5 SX CMT. PLUG AT 700' WITH 15 SX GEL & 50 SX CMT. PLUG AT 270' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS WitnessType: NONE
Date/Time Plugging Completed: 08/15/2018 5:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SAND BACK TO 3200' WITH 5 SX CMT. 1ST PLUG AT 700' WITH 13 SX GEL & 50 SX CMT. 2ND PLUG AT 270' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3436	3438		
3400	3404		
3278	3280		
3266	3268		

INVOICED
AUG 27 2018

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND CEMENTING.

Plugged through: CSG

District: 01

Signed Larry Harris
(TECHNICIAN)

RECEIVED
AUG 20 2018
KCC DODGE CITY *MD*

5A