

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-01559-00-00
Spot: W2E2SWNW Sec/Twnshp/Rge: 15-25S-14W
3300 feet from S Section Line, 4307 feet from E Section Line
Lease Name: JORDAN A Well #: 2
County: STAFFORD Total Vertical Depth: 3883 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 1700 N WATERFRONT PKY BLDG 100 S
WICHITA, KS 67206

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 3595 | | WITH 2 SX CMT |
| CIBP | | 3686 | | |
| PROD | 5.5 | 3809 | 0 | WITH 75 SX CMT |
| SURF | 8.625 | 347 | | WITH 290 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/09/2018 9:30 AM
Plug Co. License No.: 35478 Plug Co. Name: LEIKER WELL SERVICE, INC.
Proposal Rcvd. from: KEN WERNER Company: KNIGHTON OIL Phone: (316) 623-8516

Proposed Plugging Method: CIBP @ 3595' WITH 2 SX CMT. PERFORATE AT 900' & PUMP CMT TO SURFACE. FILL BACKSIDE

Plugging Proposal Received By: LARRY HARRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/09/2018 3:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SET CIBP @ 3595' WITH 2 SX CMT PLACED ON TOP. PERFORATE AT 900'. TIH WITH TBG TO 900' PUMP CMT TO SURFACE WITH 325 SX CMT. POOH WITH TBG & TOP OFF WITH 15 SX CMT. CMT HOLDING AT SURFACE.

INVOICED
AUG 27 2018

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3693 | 3883 | | |

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
AUG 20 2018
KCC DODGE CITY