

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-21356-00-01
Spot: SESESE Sec/Twnshp/Rge: 20-22S-14W
330 feet from S Section Line, 330 feet from E Section Line
Lease Name: VICE Well #: 1-20
County: STAFFORD Total Vertical Depth: 4082 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4097	0	WITH 175 SX CMT
SURF	8.625	636		WITH 375 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/07/2018 9:00 AM
Plug Co. License No.: 34044 Plug Co. Name: JD'S WELL SERVICE INC.
Proposal Rcvd. from: KEN DUEHLER Company: TRANS PACIFIC OIL Phone: (316) 262-3596

Proposed Plugging Method: PUMP 40 SX CMT WITH 250# HULLS WITH TBG AT 3650'. PULL TBG TO 875' & LOAD HOLE. PERFORATE AT 875'. CIRCULATE CMT TO SURFACE LEAVING CASING & ANNULUS FULL-200 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/07/2018 6:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

RIH WITH TBG TO 3650' & PUMP 40 SX CMT WITH 250# HULLS. POOH WITH TBG & PERFORATE AT 875'. RIH WITH TBG TO 875' & PUMP 240 SX CMT TO FILL CASING & ANNULUS TO SURFACE. CMT HOLDING STEADY AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
3700	3706		
3650	3666		

INVOICED
AUG 27 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed _____

Ken Scofield
(TECHNICIAN)

RECEIVED
AUG 20 2018
KCC DODGE CITY