

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-047-10125-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 11-25S-16W  
1632 feet from S Section Line, 1015 feet from E Section Line  
Lease Name: SMITH D Well #: 1  
County: EDWARDS Total Vertical Depth: 4363 feet

Operator License No.: 30931  
Op Name: DAYSTAR PETROLEUM, INC.  
Address: 522 N. MAIN ST PO BOX 560  
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4363	0	WITH 115 SX CMT
SURF	8.625	318		WITH 225 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/06/2018 12:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: STEVE BODINE Company: DAYSTAR PETROLEUM Phone: (620) 583-5527

Proposed Plugging Method: CIBP @ 4220'. PERFORATE AT 1050' & 360'. PLUG AT 1050' WITH 50 SX CMT WITH 100# HULLS IN LAST 25 SX CMT. PLGU AT 360' PUMP CMT INSIDE & OUT TO SURFACE.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/06/2018 7:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

Perfs:

TBG STUCK IN HOLE. TBG CUT AT 3241'. PUMP 15 SX GEL FOLLOWED BY 50 SX COMMON CMT WITH 3% CC AT 3240'. POOH WITH TBG. PERFORATE AT 1050' & 360'. TAG BOTTOM PLUG AT 2900' WITH SAND LINE. TIH WITH TBG TO 1050' & PUMP 50 SX COMMON CMT. POOH WITH TBG TO 360' & PUMP 190 SX CMT TO FILL HOLE INSIDE 5 1/2" CASING & OUTSIDE CASING. CMT REMAINING STEADY AT SURFACE.

Top	Bot	Thru	Comments
4269	4281		

INVOICED


AUG 27 2018

Remarks: USED COMMON CMT & 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
AUG 20 2018  
KCC DODGE CITY