

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23282-00-00
Spot: NESWNEW Sec/Twnshp/Rge: 21-21S-13W
4384 feet from S Section Line, 3536 feet from E Section Line
Lease Name: SAMUEL Well #: 1
County: STAFFORD Total Vertical Depth: 3700 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| PROD | 5.5 | 3700 | 1800 | WITH 175 SX CMT |
| SURF | 8.625 | 367 | | WITH 350 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/13/2018 12:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING Phone: (620) 793-3051

Proposed Plugging Method: SAND BACK TO 3580' WITH 5 SX CMT ON TOP. PLUG AT 800' WITH 10 SX GEL & 50 SX CMT. PLUG AT 420' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: HEITH WALSH Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/13/2018 2:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

Perfs:

PBTD: 3650'. SAND BACK TO 3580' WITH 5 SX CMT PLACED ON TOP. 1ST PLUG AT 800' WITH 10 SX GEL & 50 SX CMT, 2ND PLUG AT 420' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 75 SX CMT TO FILL HOLE TO SURFACE. CELLAR WAS FILLED WITH CMT. CMT HOLDING AT SURFACE.

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 3632 | 3636 | | |

INVOICED

AUG 27 2018

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed K. Scofield

(TECHNICIAN)

RECEIVED
AUG 20 2018
KCC DODGE CITY