

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20093-00-00  
Spot: NWNWNESE Sec/Twnshp/Rge: 21-26S-39W  
2540 feet from S Section Line, 1250 feet from E Section Line  
Lease Name: DOERR GU - B Well #: 2  
County: HAMILTON Total Vertical Depth: 2943 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, LLC  
Address: 600 TRAVIS STE 1400  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2700		
PROD	5.5	2943	0	WITH 850 SX CMT
SURF	8.625	604		WITH 380 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/17/2018 10:00 AM  
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP  
Proposal Rcvd. from: WES LOGAN Company: LINN OPERATING Phone: (620) 356-6961

Proposed  
Plugging  
Method:

PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/17/2018 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

Perfs:

CIBP AT 2700'. SPOT 15 SX CMT AT 2684'. FULL CIRCULATION. PUMP 50 SX CMT WITH 2% CC & 100# HULLS AT 1843' TO 1350'. FULL CIRCULATION. PULL TBG TO 646' & WAIT 1 1/2 HOURS. LOAD HOLE. CIRCULATE CMT FROM 646' TO 0' USING 65 SX CMT. TOP OFF WITH 4 SX CMT. PUMP 20 SX CMT DOWN THE ANNULUS TO 200 PSI.

Top	Bot	Thru	Comments
2740	2868'		

INVOICED


AUG 27 2018

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED CLASS C COMMON CEMENT BY BASIC.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED  
AUG 22 2018  
KCC DODGE CITY