

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20200-00-00  
Spot: SESESENW Sec/Twnshp/Rge: 30-23S-39W  
2750 feet from S Section Line, 2670 feet from E Section Line  
Lease Name: FAIRCHILD Well #: 1  
County: HAMILTON Total Vertical Depth: 2630 feet

Operator License No.: 3972  
Op Name: GLENWOOD RESOURCES, INC.  
Address: 555 17TH STREET SUITE 975  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2630	0	WITH 500 SX CMT
SURF	8.625	367		WITH 230 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/16/2018 1:30 PM  
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING  
Proposal Rcvd. from: GARY PISTER Company: EXACT WELL SERVICE Phone: (620) 384-1600

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/16/2018 5:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2050' WITH 2 SX CMT. CIBP @ 1000' OVER CASING LEAK. RUN CBL FROM 985' TO 140'. FOUND TOC @ 350'. TEST CASING TO 500 PSI. PERFORATE 3 HOLES AT 335'. INJECTION RATE 1 BPM AT 150 PSI. RUN TBG TO 950'. CIRCULATE CMT UP THE 4 1/2" CASING & 4 1/2" X 8 5/8" ANNULUS TO SURFACE USING 105 SX CMT LEAVING THE CASING AND ANNULUS FULL OF CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
2565	2570		

INVOICED  
AUG 27 2018

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY GLOBAL.

Plugged through: TBG

District: 01

Signed

*Ken Jehlik*  
5/8

(TECHNICIAN)

RECEIVED  
AUG 22 2018  
KCC DODGE CITY

*MR*