

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20197-00-00
Spot: SESESENW Sec/Twnshp/Rge: 19-23S-39W
2781 feet from S Section Line, 2771 feet from E Section Line
Lease Name: FOTOPOLOUS Well #: 1
County: HAMILTON Total Vertical Depth: 2646 feet

Operator License No.: 3972
Op Name: GLENWOOD RESOURCES, INC.
Address: 555 17TH STREET SUITE 975
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1000		
CIBP		2000		WITH 2 SX CMT
PROD	4.5	2646	0	WITH 500 SX CMT
SURF	8.625	342		WITH 280 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/16/2018 8:00 AM
Plug Co. License No.: 99974 Plug Co. Name: GLOBAL CEMENTING
Proposal Rcvd. from: GARY PISTER Company: EXACT WELL SERVICE Phone: (620) 384-1600

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/16/2018 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2000' WITH 2 SX CMT. CIBP AT 1000' OVER CASING LEAK. RUN CBL FROM 995' TO 230'. TOC @ 366'. TEST CASING TO 500#. PERFORATE 3 HOLES AT 360'. INJECTION RATE 2 1/2 BPM AT 0 PSI. RAN TBG TO 965'. CIRCULATE CMT TO SURFACE UP THE 4 1/2" AND 4 1/2" X 8 5/8" ANNULUS USING 115 SX CMT LEAVING BOTH FULL OF CMT. STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
2584	2591		

INVOICED
AUG 27 2018

Remarks: **COMPIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY GLOBAL OILFIELD SERVICE.

Plugged through: TBG

District: 01

Signed

Ken Jehlik
SA

(TECHNICIAN)

RECEIVED
AUG 22 2018
KCC DODGE CITY