

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23992-00-00
Spot: NENENW Sec/Twnshp/Rge: 18-22S-12W
4912 feet from S Section Line, 2983 feet from E Section Line
Lease Name: DAWN NELL Well #: 1-18
County: STAFFORD Total Vertical Depth: 3785 feet

Operator License No.: 6039
Op Name: L. D. DRILLING, INC.
Address: 7 SW 26TH AVE
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3757	2222	WITH 180 SX CMT
SURF	8.625	336		WITH 350 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/16/2018 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: MIKE KASSELMAN Company: L.D. DRILLING Phone: (620) 793-3051

Proposed Plugging Method: SAND BACK TO 3575' WITH 5 SX CMT ON TOP. PLUG AT 730' WITH 10 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 60' WITH 15 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/20/2018 12:00 PM KCC Agent: KEN SCOFIELD

Actual Plugging Report:

SAND BACK TO 3600' WITH 5 SX CMT PLACED ON TOP. 1ST PLUG AT 730' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG PULL CASING TO 360' & PUMP 50 SX CMT WITH NO RETURNS OF FLUID TO SURFACE. PULL REMAINING 5 1/2" CASING FROM HOLE. WAIT & TAG CMT, 8/17/18; TAG CMT AT 920'. RIH WITH TBG TO 720' & ESTABLISH CIRCULATION WITH WATER. PUMP 50 SX CMT. LOST CIRCULATION WHILE PUMPING CMT. POOH WITH TBG TO 360' & TRY TO CIRCULATE WATER WITHOUT SUCCESS. TIH WITH TBG TO 600' & PUMP 50 SX CMT. FLID GOT WITHIN 3' OF SURFACE BUT FELL FAST. 8/20/18; TAG CMT AT 920'. RIH WITH TBG TO 720' & PUMP WATER & 450# HULLS FOLLOWED BY 5 SX GEL. CIRCULATION ESTABLISHED. PUMP 50 SX COMMON CEMENT WITH 3% CC WITH 50# HULLS. GOOD CIRCULATION TO SURFACE. POOH WITH TBG TO 360' & PUMP 50 SX COMMON CMT WITH 3% CC. GOOD RETURNS. POOH TO 40' & PUMP 30 SX CMT TO FILL HOLE. CELLAR WAS FILLED WITH CMT. CMT HOLDING AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
3682	3684		

INVOICED
AUG 27 2018

Remarks: USED 60/40 POZMIX 4% GEL & COMMON CMT WITH 3% CC BY COPELAND ACID.

Plugged through: TBG

District: 01

Signed [Signature]
(TECHNICIAN)

RECEIVED
AUG 23 2018
KCC DODGE CITY