

2-070829

6-25

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

A PI NUMBER: Drilled 1963

SE NE SW, SECTION 8 TOWNSHIP 20S RANGE 10 W

OPERATOR LICENSE # 31925  
OPERATOR Quality Well Service  
NAME & 249 Beth Drive  
ADDRESS Sterling, Ks. 67579-9048

1650 FEET FROM S SECTION LINE  
2970 FEET FROM E SECTION LINE  
LEASE NAME: Bayer # 1  
COUNTY: Rice  
WELL TOTAL DEPTH: 3367 *109.24*  
PIPE: 5 1/2" - 3361  
SURFACE CASING: 8 5/8" - 183

ABANDONED OIL WELL XX GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Quality Well Service Inc.  
ADDRESS: 249 Beth Drive, Sterling, Ks. 67579-9048 LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: 10:30 A.M. DAY: 25th MONTH: June YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM: Joe Mase  
COMPANY NAME: Quality Well Service Inc. PHONE: 316-727-3410  
WERE: Sand to 3300 and 5 sacks  
35 sacks - 1300'  
35 sacks - 800'  
250' to 0

RECEIVED  
KANSAS CORPORATION COMMISSION

JUL 09 1999

CONSERVATION DIVISION  
WICHITA, KS

PLUGGING PROPOSAL RECEIVED BY: Jack Luthi  
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( XX ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 3:30 DAY: 25th MONTH: June YEAR: 1999

ACTUAL PLUGGING REPORT: Sanded bottom to 3800' and 5 sacks. Shot 5 1/2" casing off at 2000'. Pulled to 1300'. Pumped 35 sacks, pulled to 800. Pumped 35 sacks, pulled to 250' and circulated cement to surface.

REMARKS: Allied # 9123 60/40 4%

I DID OBSERVE THIS PLUGGING.

*Jack Luthi*  
Jack Luthi

FORM CP-2/3  
REV. 3/90

PIRT

INVOICED

DATE 2-9-99

WV. NO. 60028

6-25 AUG 27 1999