

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-159-20,541.6000

W/2W/2 SW SECTION 8 TOWNSHIP 20S RANGE 10W

OPERATOR LICENSE # 31925
OPERATOR Quality Well Service
NAME & 249 Beth Drive
ADDRESS Sterling, Ks. 67579-9048

1320 FEET FROM S SECTION LINE
4620 FEET FROM E SECTION LINE

LEASE NAME: Bayer # 3
COUNTY: Rice 108.94
WELL TOTAL DEPTH: 3352
PIPE: 5 1/2" 3342
SURFACE CASING: 8 5/8" - 191

ABANDONED OIL WELL XX GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Quality Well Service
ADDRESS: 249 Beth Dr., Sterling, Ks.67579-9048 LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 9:00 am DAY: 24th MONTH: June YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM: Richard McIntyre

COMPANY NAME: Quality Well Service PHONE: 316-727-3410
WERE: Sand to 3287 and 5 sacks
35 sacks 1300'
35 sacks 800'
250' to 0

PLUGGING PROPOSAL RECEIVED BY: Jack Luthi

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { XX } PART { } NONE { }

COMPLETED: HOUR: 5:00 pm DAY: 24th MONTH: June YEAR: 1999

ACTUAL PLUGGING REPORT: Sand bottom to 3287 and 5 sacks of common.
Shot 5 1/2" casing off at 2420. Pulled to 1300' pumped 35 sacks.
Pulled to 800' pumped 35 sacks. Pulled to 250' circulate cement to
surface.

REMARKS: Allied # 1927 60/40 4 %

I DID OBSERVE THIS PLUGGING.

Jack Luthi

FORM CP-2/3
REV. 3/90

INVOICED

PIRT DATE **JUL 02 1999**

INV. NO. 60012

6-24 AUG 27 1999