

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-019-19804-00-00  
Spot: NESENW Sec/Twnshp/Rge: 36-34S-11E  
3566 feet from S Section Line, 2683 feet from E Section Line  
Lease Name: O K SPURLOCK Well #: 6  
County: CHAUTAUQUA Total Vertical Depth: 1199 feet

Operator License No.: 8387  
Op Name: CUSTER, BILL L.  
Address: 2138 DALTON RD  
PERU, KS 67360

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1199		
SURF	8.625	40		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Rcvd. from: JO CUSTER Company: \_\_\_\_\_ Phone: (620) 725-3925

Proposed Plugging Method: PLUG ACCORDING TO KCC SPECIFICATION

Plugging Proposal Received By: DUANE SIMS WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/21/2018 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1188' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 650' and 350'. Ran back into 650' and spotted 20 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 140 sacks of cement with 3% gell was used to plug this well. Well was cut off and location restored.

RECEIVED  
KCC DIST # 3  
AUG 28 2018  
CHANUTE, KS

DS


INVOICED  
AUG 28 2018

Remarks: WELL WAS PLUGGED BECAUSE IT WAS LAST WELL ON THEIR LICENSE. LET LICENSE EXPIRE.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)