

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-22614-00-00
Spot: SESENW Sec/Twnshp/Rge: 19-28S-9E
2672 feet from S Section Line, 2719 feet from E Section Line
Lease Name: MERIEM Well #: 1-19
County: ELK Total Vertical Depth: 2975 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	42		50 SX

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 06/14/2018 12:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Revd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 50' plug at TD. 50' plug at 2540'. 50' plug at 1773'. 500' to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 06/14/2018 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Dry hole. Hooked onto drill pipe and spotted 50' plug at 2900'. Pulled up to 2540' and spotted 50' plug. Pulled up to 1773' and spotted 50' plug. Pulled up to 500' and circulated cement to surface. Pulled drill pipe and topped well off. Rat hole and mouse hole were also filled with cement. 220 sacks of 60/40 pozmix with 4% gel were used to plug this well. Well was cut off and location restored.

Perfs:

RECEIVED
KCC DIST # 3
AUG 28 2018
CHANUTE, KS

INVOICED
AUG 28 2018

DS

Remarks:

Plugged through: DP

District: 03

Signed _____

(TECHNICIAN)