

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-22100-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 17-30S-6W
330 feet from S Section Line, 2310 feet from E Section Line
Lease Name: T-BAR LAND AND CATTLE Well #: 1
County: KINGMAN Total Vertical Depth: 4538 feet

Operator License No.: 31337
Op Name: WILDCAT OIL & GAS LLC
Address: PO BOX 40
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	4450		
PROD	7.875	4534		275 SX
SURF	8.625	208		200 SX
T1	2.875	3574		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/15/2018 12:00 AM
Plug Co. License No.: 34422 Plug Co. Name: RED ROCK ENERGY SERVICES INC.
Proposal Revd. from: ANDREW Company: RED ROCK ENERGY SERVICES Phone: (620) 532-1895

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/15/2018 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PULLED RODS & TUBING FROM WELL AND LAYED OUT. SET CIBP @ 3515' & CAPPED WITH 2 SKS CEMENT. SHOT & RECOVERED CASING FROM 2635' & LAYED OUT. RAN 2 7/8" TUBING TO 1160', PUMPED 10 SKS GEL & 40 SX COMMON 3% CACL CEMENT. TAGGED CEMENT AFTER 2 HOURS. TOC AT 950', PUMPED 35 SX AT 747'. PULLED TO 312' & ~~PULLED~~ **PUMPED** 110 SX CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4452	4466	CSG	
3568	3571	CSG	

INVOICED
AUG 29 2018

Remarks: QUALITY WELL SERVICE COM 3% CACL

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)