

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-24258-00-01  
Spot: SWNWNE Sec/Twnshp/Rge: 26-30S-4E  
4088 feet from S Section Line, 2129 feet from E Section Line  
Lease Name: WILCOX Well #: 1-A  
County: COWLEY Total Vertical Depth: 2962 feet

Operator License No.: 31302  
Op Name: JONES & BUCK DEVELOPMENT, LLC  
Address: PO BOX 68  
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		2892		PERMITTED PACKER ARROW J @ 2892
PROD	4.5	2952		150 SX
SURF	8.625	201		100 SX
T1	2.375	2892		PERMITTED TUBING @ 2892

Well Type: EOR UIC Docket No: E32372.1 Date/Time to Plug: 08/06/2018 8:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Revd. from: PJ BUCK Company: Phone: (620) 725-3636

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/06/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/1" TUBING @ 2900', ELMORES MIXED & PUMPED 1 SX GEL W/6 BBLs WATER AND 10 SXS CLASS A COMMON CEMENT & DISPLACED IN CASING. TAGGED CEMENT @ 2762'. CUT CASING @ 1200', LAID DOWN 36 JOINTS OF 4.5" CASING. RIH W/1" @ 255', ELMORES ESTABLISHED CIRCULATION, MIXED & PUMPED 128 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
2949	2954	CSG	
2935	2945	CSG	

INVOICED

AUG 29 2018

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

✓