

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-035-24617-00-00
Spot: NWSESENE Sec/Twnshp/Rge: 17-30S-5E
3080 feet from S Section Line, 440 feet from E Section Line
Lease Name: TEMPLAR Well #: 17-2
County: COWLEY Total Vertical Depth: 3260 feet

Operator License No.: 31302
Op Name: JONES & BUCK DEVELOPMENT, LLC
Address: PO BOX 68
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3252		125 SX
SURF	8.625	222		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/06/2018 8:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: PJ BUCK Company: _____ Phone: (620) 725-3636

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/06/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/1" TUBING @ 3020', ELMORES MIXED & PUMPED 1 SX GEL W/ 6 BBLs WATER & 12 SXS CLASS A COMMON CEMENT AND DISPLACED IN CASING. LET SET 2 HOURS, TAGGED CEMENT @ 2955'. CUT CASING @ 1175'. LAYED 5 1/2' CASING DOWN. RIH W/ 1' TUBING @ 272'. ELMORES ESTABLISHED CIRCULATION MIXED & PUMPED 108 SXS CLASS A COMMON TO SURFACE. CEMENT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
3079	3089	CSG	

INVOICED
AUG 29 2018

Remarks:

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER

(TECHNICIAN)

JK