

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-19567-00-00  
Spot: SESWNWSE Sec/Twnshp/Rge: 19-30S-4E  
1343 feet from S Section Line, 2042 feet from E Section Line  
Lease Name: HOUSER Well #: 2  
County: COWLEY Total Vertical Depth: 2883 feet

Operator License No.: 33556  
Op Name: DRAKE EXPLORATION, LLC  
Address: 15894 294TH CIR #19  
ARKANSAS CITY, KS 67005

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2832		0 SX
SURF	15.5	195		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/01/2018 8:00 AM  
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.  
Proposal Revd. from: DARREN BROYLES Company: \_\_\_\_\_ Phone: (620) 441-7223

Proposed Plugging Method: AS PER KCC RULES & REGS/ CLASS A COMMON CEMENT. CEMENT TO 2750' & TAG PERF & CIRCULATE 250'-0'.

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/07/2018 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

RIH W/TUBING @ 2780', ELMORES CEMENTING, MIXED AND PUMPED 1.5 SX GEL WITH 6 BBLs WATER & 20 SXS CLASS A COMMON CEMENT & DISPLACED IN CASING. SDON. TAGGED CEMENT @ 2540'. RIH ON WIRELINE, PERFORATED SQUEEZE HOLES (4 HOLES) 260'-261'. RIH WITH TUBING @ 270', ELMORES MIXED & PUMPED 22 SXS CLASS A COMMON 3% CC & DISPLACED IN CASING. LET CEMENT SET, RIH W/TUBING @ 250', ELMORES CEMENTING MIXED & PUMPED 300 SXS CLASS A COMMON & DISPLACED IN CASING. CEMENT DID NOT CIRCULATE. TAGGED CEMENT AT 70' INSIDE PRODUCING STRING & 80' ON BACKSIDE. RIH WITH TUBING ON BACKSIDE, @ 80', ELMORES MIXED & PUMPED 55 SXS TO SURFACE. RIH WITH TUBING ON INSIDE @ 65'. ELMORES MIXED & PUMPED 10 SXS TO SURFACE. CEMENT CIRCULATED IN ALL STRINGS. P&A COMPLETE.

INVOICED

AUG 29 2018

Remarks: DENIED TA

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)

SK