

Kansas Corporation Commission

District Plugging Report

API Well Number: 15-133-19459-00-00  
 Spot: SW/SW Sec 28 Twp 27 S Rng 19  E /  W  
420 Feet from  N /  S Line of Section  
4266 Feet from  E /  W Line of Section  
 GPS: Lat: 37.661157 Long: 95.339744 Date: 3/17/14  
 Lease Name: Dillow Well #: 4 (DIL 15)  
 County: Neosho Total Vertical Depth: 590 feet

Operator License No: 101  
 Op Name: KANSAS CORPORATION COMMISSION  
 Address 1: 266 N MAIN STE 220  
 Address 2: \_\_\_\_\_  
 City: WICHITA  
 State: KS Zip Code: 67202 - \_\_\_\_\_

String	Size	Depth	Pulled	Comments
<u>SURF - Casing</u>	<u>6.000</u>			
<u>PROD - Casing</u>	<u>2.000</u>			

Well Type: OG - Oil & Gas (oil) UIC Docket No.: \_\_\_\_\_ Date/Time to Plug: 7/5/18 / \_\_\_\_\_  
 Plug Co License No.: 33749 Plug Co. Name: KWS  
 Proposal Rcvd from: Mike Kepley Company Name: \_\_\_\_\_ Phone: (620) 431-9272

Proposed Plugging Report: CLEAN OUT WELLS TO BOTTOM. PUMP FULL OF PORTLAND CEMENT, INSIDE AND OUTSIDE OF CASING. IF CEMENT IS PRESENT IN THE ANNULUS, CASING SHOULD BE PERFORATED IN AT LEAST 2 INTERVALS, UNLESS WELL IS DOCUMENTED AS ALT. 2 COMPLETION.

Plugging Proposal Received By: Tony Anderson Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 7/5/18 / \_\_\_\_\_ KCC Agent: Tony Anderson

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
<p>CLEARED TREES AND BRUSH AROUND WELL. TRIED TO RUN 1" BUT COULD NOT GET DOWN. MOVED DRILL RIG IN AND DRILLED INSIDE 2". DRILLED THRU CEMENT, THEN DRILLED SCALE TO 350'. WASHED DOWN TO 590' INSIDE AND 470' OUTSIDE. PUMPED 182 SACKS OF CEMENT. THE LOCATION WAS RESTORED.</p>				

Remarks: Control#20170014-004 ;Nad83;GPS by Tom, Frank, Tony

Plugged Thru: \_\_\_\_\_ Plugged Due to Compliance Issue:  Yes  No

District: 03  
 KCC WICHITA  
 JUL 26 2018  
 RECEIVED  
Tony Anderson  
 (Technician)  
 Form: District Plugging Report - \_\_\_\_\_