

Kansas Corporation Commission
District Plugging Report

API Well Number: 15-133-19662-00-00
 Spot: SW/SW Sec 28 Twp 27 S Rng 19 E / W
569 Feet from N / S Line of Section
4435 Feet from E / W Line of Section
 GPS: Lat: 37.661574 Long: 95.340329 Date: 3/17/16
 Lease Name: Dillow Well #: 7
 County: Neosho Total Vertical Depth: 630 feet

Operator License No: 101
 Op Name: KANSAS CORPORATION COMMISSION
 Address 1: 266 N MAIN STE 220
 Address 2: _____
 City: WICHITA
 State: KS Zip Code: 67202

Well Type: OG - Oil & Gas (oil) UIC Docket No.: _____ Date/Time to Plug: 1/11/18
 Plug Co License No.: 33749 Plug Co. Name: KWS
 Proposal Rcvd from: Mike Kepley Company Name: _____ Phone: (420) 431-9212

Proposed Plugging Report: **CLEAN OUT WELLS TO BOTTOM. PUMP FULL OF PORTLAND CEMENT, INSIDE AND OUTSIDE OF CASING. IF CEMENT IS PRESENT IN THE ANNULUS, CASING SHOULD BE PERFORATED IN AT LEAST 2 INTERVALS, UNLESS WELL IS DOCUMENTED AS ALT. 2 COMPLETION.**

Plugging Proposal Received By: Tony Anderson Witness Type: COMP - Complete 100%
 Date/Time Plugging Completed: 1/8/18 KCC Agent: Tony Anderson
 Actual Plugging Report: 1/11/18

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
<p>CLEAR AROUND THE WELL. DUG DOWN AND CUT OFF 2" TO GET IT STRAIGHT. COULD NOT GET ANY SIZE PIPE DOWN INSIDE. WASH DOWN OUTSIDE TO 630' AND GOT COMMUNICATION UP 2". PUMPED 195 SACKS OF CEMENT. WASHED TO 30' IN 4" CASING BESIDE THE WELL AND ALSO FILLED WITHE CEMENT. THE LOCATION WAS RESTORED.</p>	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____

Remarks: Control#20170014-007;Nad83;GPS by Tom, Frank, Tony

Plugged Thru: _____ Plugged Due to Compliance Issue: Yes No

District: 03
 RECEIVED
 KANSAS CORPORATION COMMISSION
 FEB 06 2018
 CONSERVATION DIVISION
 WICHITA, KS
Tony Anderson
 (Technician)
 Form: District Plugging Report - _____