

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 11-30-82

NE SE SW, SECTION 19 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 5734 990 FEET FROM S SECTION LINE
2970 FEET FROM E SECTION LINE

OPERATOR CULVER & GROUNDS OIL PROP
NAME & P O BOX 793
ADDRESS MCPHERSON KS 67460

LEASE NAME: LINDHOLM B-1 109.36
COUNTY: MCPHERSON
WELL TOTAL DEPTH: 3365'

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 212'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: KELSO CASING PULLING
ADDRESS: P O BOX 347, CHASE KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 10:30 DAY: 16 MONTH: 12 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: GENE GROUNDS

COMPANY NAME: CULVER & GROUNDS OIL PROP PHONE: 316-241-5213

WERE: SAND TO 3220' & TOP W/5 SX CMT - SHOOT PIPE OFF & PULL
PIPE TO 825' - SPOT 35 SX CMT - PULL PIPE TO 360' &
CIRC CMT TO SURF
5-1/2" CSG @ 3364' - PERFS 3268'-3340'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 13:00 DAY: 16 MONTH: 12 YEAR: 1993

ACTUAL PLUGGING REPORT:
SANDED TO 3220' & TOPPED W/5 SX CMT - SHOT PIPE OFF @
2617' & PULLED 44 JTS - SPOTTED 35 SX CMT @ 840' -
PULLED 11 JTS & CIRC 130 SX CMT TO SURF FROM 400'
RETRIEVED 2617 OF 5-1/2" CSG

REMARKS: USED 60/40 POZ W/4% GEL BY ALLIED #3205

RECEIVED
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

MS

Michael R. Wilson

(AGENT)

DEC 22 1993

FORM CP-2/3

REV. 3/90

CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 12-29-93

INV. NO. 39580

12-16

DLW