

4-23

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-113-21,166.00.00

N/2N/2SE, SECTION 19 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 5734 2310 FEET FROM S SECTION LINE

1320 FEET FROM E SECTION LINE

OPERATOR Culver Grounds Oil Prod.
NAME & P.O.Box 793
ADDRESS McPherson KS 67460

LEASE NAME: Lindquist 10-2

COUNTY: McPherson 110.50

WELL TOTAL DEPTH: 3400(3387)PB

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 213'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Kelso Casing Pulling Inc.
ADDRESS: P.O.Box 347 Chase KS 67584-0347 LICENSE: _____

COMPANY TO PLUG AT: HOUR: 13:00 DAY: 23 MONTH: 4 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: Mike Kelso

COMPANY NAME: Kelso Casing Pulling Inc. PHONE: 316-938-2943

WERE: Sand to 3240' & top with 5sx of cmt - Shoot pipe off
and 35sx cmt @ 775' & circ cmt from 300' to surface.
5-1/2" @ 3398' - Elev=1544'

PLUGGING PROPOSAL RECEIVED BY: Ralph Tittel

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 14:30 DAY: 23 MONTH: 4 YEAR: 1993

RECEIVED
STATE CORPORATION COMMISSION

ACTUAL PLUGGING REPORT:

Sanded to 3240' & topped w/ 5sx cmt - Shot pipe off @
2624' - Pulled 5-1/2" & spotted 35sx cmt @ 775' & circ
95sx cmt from 300' to the surface - Circ hole before
stripping top 2 plugs - Recovered 2624' of 5-1/2" casing

REMARKS: Used 60/40 poz w/ 4%gel by Allied - Invoice #5971

INVOICED I DID OBSERVE THIS PLUGGING.

DATE 6-2-93

INV. NO. 37793

Michael R. Wilson
Michael R. Wilson (AGENT)