

4-5

2-010074

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: 15-113-21,099.00.00

W2 NW NW, SECTION 19 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 5057 4620 FEET FROM S SECTION LINE  
4950 FEET FROM E SECTION LINE

OPERATOR VOIGT OIL & GAS INC  
NAME & RR 3 BOX 33C  
ADDRESS MCPHERSON KS 67460

LEASE NAME: VIRGIL ANDERSON 2

COUNTY: MCPHERSON 110.50

WELL TOTAL DEPTH: 3400' (3330')

PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 220'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SLD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: SUNFLOWER WELL SERVICE  
ADDRESS: P O BOX 341, CANTON, KS LICENSE: 30280

COMPANY TO PLUG AT: HOUR: 15:00 DAY: 5 MONTH: 4 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: \_\_\_\_\_

COMPANY NAME: VOIGT OIL & GAS INC PHONE: 316-227-3241

WERE: SAND TO 3225' & TOP W/5/SX CMT - SHOOT PIPE OFF - PULL  
PIPE TO 800' & SPOT 35 SX CMT - PULL PIPE TO 400' &  
CIRC CMT TO SURF  
5-1/2" CSG @ 3399' - PERFS 3277' TO 3344'

PLUGGING PROPOSAL RECEIVED BY: \_\_\_\_\_

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART (  ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 19:15 DAY: 5 MONTH: 4 YEAR: 1995

ACTUAL PLUGGING REPORT:

SANDED TO 3225' & TOPPED W/5/SX CMT - SHOT PIPE OFF @  
1996' - PULLED PIPE TO 861' & SPOTTED 35 SX CMT -  
PULLED PIPE TO 430' & CIRC 170 SX CMT TO SURF -  
RETRIEVED 1996' OF 5-1/2" CSG

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 28 1995

REMARKS: USED 60/40 POZ W/4% GEL BY UNITED #1051

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson  
Michael R. Wilson (AGENT)

CONSERVATION DIVISION  
WICHITA, KS

INVOICED

DATE 5-8-95

INV. NO. 42793

FORM CP-2/3  
REV. 3/90

4-5 JUN 21 1995

aw