

10-15

RECEIVED  
KANSAS CORPORATION COMMISSION

2-

OCT 27 1993

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

CONSERVATION DIVISION  
WICHITA, KS

API NUMBER: 15-113-21,084 · 00 · 00  
100' W OF NE NW, SECTION 19 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 5734 4620 FEET FROM S SECTION LINE  
3400 FEET FROM E SECTION LINE

OPERATOR CULVER & GROUNDS OIL PROP  
NAME & P O BOX 793  
ADDRESS MCPHERSON KS 67460

LEASE NAME: ANDERSON 8-2  
COUNTY: MCPHERSON 110.30  
WELL TOTAL DEPTH: 3394' (3367')

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 219'

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: KELSO CASING PULLING INC  
ADDRESS: P O BOX 347, CHASE KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 14:00 DAY: 15 MONTH: 10 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: GENE GROUNDS  
COMPANY NAME: CULVER & GROUNDS PHONE: 316-241-1179

WERE: SAND TO 3245' & 5 SX - SHOOT OFF PIPE - PULL PIPE &  
SPOT 35 SX CMT @ 800' - 35 SX @ 400' - CIRC CMT FROM  
270' TO SURFACE.  
PERFS @ 3298'-3358' - 5-1/2" CSG @ 3393'

PLUGGING PROPOSAL RECEIVED BY: M L KORPHAGE

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART ( X ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 17:15 DAY: 15 MONTH: 10 YEAR: 1993

ACTUAL PLUGGING REPORT:  
SANDED TO 3200' & TOPPED W/5 SX CMT - SHOT PIPE OFF  
@ 2636' - PULLED PIPE TO 800' & SPOTTED 35 SX CMT -  
PULLED PIPE TO 400' & SPOTTED 35 SX CMT - PULLED PIPE  
TO 270' & CIRC 60 SX CMT TO SURF - ON 10/19/93 TOPPED  
OFF TOP PLUG W/75 SX CMT - RETRIEVED 2636' 5-1/2" CSG

REMARKS: USED 60/40 POZ 4% GEL BY ALLIED #3735 AND #3754

IF YOU DID NOT OBSERVE THIS PLUGGING.  
**INVOICED**

DATE NOV 03 1993  
INV. NO. 39097

Michael R Wilson  
MICHAEL R WILSON (AGENT)