

11-9

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-113-21,018.00.00
N/2 N/2 NE, SECTION 19 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 5734 4950 FEET FROM S SECTION LINE
1320 FEET FROM E SECTION LINE

OPERATOR CULVER & GROUNDS OIL PROP
NAME & P O BOX 793
ADDRESS MCPHERSON KS 67460

LEASE NAME: NELSON #7-2
COUNTY: MCPHERSON
WELL TOTAL DEPTH: 3387' 110.07

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 218'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: KELSO CASING PULLING
ADDRESS: CHASE KS LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 1:30 DAY: 9 MONTH: 11 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: KELSO PHONE: _____

WERE: 50 SX ON BOTTOM - 50 SX @ 850' - 400' TO SURFACE RECEIVED
KANSAS CORPORATION COMMISSION

NOV 19 1993

PLUGGING PROPOSAL RECEIVED BY: _____ CONSERVATION DIVISION
WICHITA, KS

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 5:00 DAY: 9 MONTH: 11 YEAR: 1993

ACTUAL PLUGGING REPORT:
CASING PARTED @ 400' - RAN TUB IN TO BRIDGE @ 900'
& SHOT 3 HOLES IN CSG @ 900' - PUMPED 50 SX CMT -
WAITED 2 HRS - TAGGED CMT @ 820' - PULLED TUB TO 400'
& CIRC CMT TO SURF

REMARKS: ALLIED #3788 60/40 4%

I DID OBSERVE THIS PLUGGING.
INVOICED

DATE NOV 22 1993

INV. NO. 39271

15/

Jack Luthi (AGENT)