

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

NOV 22 1991

CONSERVATION DIVISION  
WICHITA, KS

API NUMBER: 15-113-20,873<sup>00.00</sup> D-20,132

SW NE, SECTION 19 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 5734 3300 FEET FROM S SECTION LINE  
2310 FEET FROM E SECTION LINE

OPERATOR Culver & Grounds  
NAME & 1432 Ranch Road  
ADDRESS McPherson, KS 67460

LEASE NAME: Nelson "C" #1 SWD  
COUNTY: McPherson  
WELL TOTAL DEPTH: 4012' 130.39

CONDUCTOR PIPE: " @ ' "  
SURFACE CASING: 8-5/8" @ 206'

ABANDONED OIL WELL \_\_\_\_\_ GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD X D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Culver & Grounds  
ADDRESS: \_\_\_\_\_ LICENSE: \_\_\_\_\_

COMPANY TO PLUG AT: HOUR: 11:00 DAY: 14 MONTH: 11 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Gene Grounds  
COMPANY NAME: \_\_\_\_\_ PHONE: \_\_\_\_\_

WERE: Plastic tubing in the hole to 2250' - ran rods with fishing tool - lost tool & 68 rods - fill with cement.

PLUGGING PROPOSAL RECEIVED BY: Jack Luthi

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( X ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: \_\_\_\_\_ DAY: 14 MONTH: 11 YEAR: 1991

ACTUAL PLUGGING REPORT:  
Pumped 200 sx common; then 600 lbs. hulls mixed in with cmt - pumped another 200 sx - shut down for 45 min; still couldn't fill - shut down over nite - found cmt @ 522' - used 143 sx to surface - tied to back side - took 67 sx - 100 lbs press shut in.

REMARKS: Halliburton #978356 250 sx com; 270 sx 60/40 4%

I DID OBSERVE THIS PLUGGING.

**INVOICED**

Jack Luthi  
Jack Luthi (AGENT)

DATE 12-5-91  
WV. NO. 33955

DW