

1-9

2-010063

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER: 15-113-20,832-00.00

SE SW NW , SECTION 19 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 5057

2310 FEET FROM <sup>N</sup> SECTION LINE  
990 FEET FROM <sup>W</sup> SECTION LINE

OPERATOR VOIGT OIL & GAS CO INC  
NAME & RR 3, BOX 33-C  
ADDRESS MCPHERSON KS 67460

RECEIVED  
KANSAS CORPORATION COMMISSION  
110.76  
MAR 10 1995  
CONSERVATION DIVISION  
WICHITA, KS

LEASE NAME: VIRGIL ANDERSON #1  
COUNTY: MCPHERSON  
WELL TOTAL DEPTH: 3408' (3293')

PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 224'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SMD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: SUNFLOWER WELL SERVICE  
ADDRESS: P O BOX 341, CANTON KS 67428 LICENSE: 30280

COMPANY TO PLUG AT: HOUR: 14:00 DAY: 9 MONTH: 1 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: RICHARD H. VOIGT

COMPANY NAME: VOIGT OIL & GAS CO INC PHONE: 913-227-3241

WERE: SAND TO 3225' AND TOP W/5 SX CMT - SHOOT PIPE OFF &  
PULL TO 775' & SPOT 35 SX CMT - PULL PIPE TO 350' &  
CIRC CMT TO SURF.  
5-1/2" CSG @ 3380'  
PERFS @ 3276' TO 3291'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R. WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL ( \_\_\_\_\_ ) PART (  ) NONE ( \_\_\_\_\_ )

COMPLETED: HOUR: 16:15 DAY: 9 MONTH: 1 YEAR: 1995

ACTUAL PLUGGING REPORT:  
SANDED TO 3225' & TOPPED W/5 SX CMT - SHOT PIPE OFF @  
3100' & PULLED PIPE TO 807' & SPOTTED 35 SX CMT -  
PULLED PIPE TO 340' & CIRC 130 SX CMT TO SURF -  
RETRIVED 3100' OF 5-1/2" CSG

REMARKS: USED 60/40 POZ W/4% GEL BY UNITED #1754

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson  
Michael R. Wilson (AGENT)

INVOICED

DATE MAR 14 1995

INV. NO. 42411

FORM CP-2/3  
REV. 3/90

1-9 APR 25 1995 JUN 21 1995