

4-19

2- 2-0604

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-113-20,744.00.00

N/2 SE, SECTION 19 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 5734 1950 FEET FROM S SECTION LINE

1320 FEET FROM E SECTION LINE

OPERATOR Culver&Grounds Oil Prod. Inc.
NAME & P.O.Box 793
ADDRESS McPherson KS 67460

LEASE NAME: Linguist 10-1

COUNTY: McPherson 109.68

WELL TOTAL DEPTH: 3375 P.B. 3344'

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 02 1993

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 174'-135sx

CONSERVATION DIVISION
WICHITA, KS
ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Kelso
ADDRESS: Chase KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 8:00a DAY: 17 MONTH: 4 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: Mike K.

COMPANY NAME: Kelso PHONE: _____

WERE: Sand to 3220' - c/w 5sx cmt - 35sx @ 775' - 300' to surf-circ.

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 17:00 DAY: 19 MONTH: 4 YEAR: 1993

ACTUAL PLUGGING REPORT:

Sanded to 3220' - c/w 5sx cmt - Recovered - 1415' - 5-1/2" - Pull to 775' spot 35sx cmt - pull to 300' - cir cmt to surf.

Allied # 1326 - 180sx 60/40 - 4%gel

REMARKS: _____

I DID OBSERVE THIS PLUGGING.

INVOICED

Ralph Tittel
Ralph Tittel (AGENT)

DATE 6-3-93

INV. NO. 37810

FORM CP-2/3

REV. 3/90

DW