

10-19

2-

RECEIVED
KANSAS CORPORATION COMMISSION

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

OCT 27 1993

CONSERVATION DIVISION
WICHITA, KS

API NUMBER: 15-113-20,710 · 00 · 00

E/2 SE NW, SECTION 19 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 5734 3300 FEET FROM S SECTION LINE
2970 FEET FROM E SECTION LINE

OPERATOR CULVER & GROUNDS OIL PROP
NAME & P O BOX 793
ADDRESS MCPHERSON KS 67460

LEASE NAME: ANDERSON 8-1
COUNTY: MCPHERSON 109.85
WELL TOTAL DEPTH: 3380' (3363')

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 174'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: KELSO CASING PULLING INC
ADDRESS: P O BOX 347, CHASE KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 14:00 DAY: 19 MONTH: 10 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: GENE GROUNDS
COMPANY NAME: CULVER & GROUNDS PHONE: 316-241-1179

WERE: SAND TO 3215' & TOP W/5 SX CMT - SHOOT PIPE OFF & PULL
TO 800' - SPOT 35 SX @ 800' - PULL TO 400' & CIRC CMT
TO SURF
PERFS @ 3269'-3304' - 5-1/2" CSG @ 3379'

PLUGGING PROPOSAL RECEIVED BY: MIKE WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART () NONE (_____)

COMPLETED: HOUR: 16:30 DAY: 19 MONTH: 10 YEAR: 1993

ACTUAL PLUGGING REPORT:
SANDED TO 3305' & TOPPED W/5 SX CMT - SHOT PIPE OFF
@ 2711' - PULLED PIPE TO 800' & SPOTTED 35 SX CMT -
PULLED PIPE TO 400' & CIRC 115 SX CMT TO SURF.
RETRIEVED 2711' OF 5-1/2" CSG

REMARKS: USED 60/40 POZ 4% GEL BY ALLIED #3754

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE NOV 03 1993

INV. NO. 390.98

MICHAEL R WILSON (AGENT)