

11-9

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-113-20, 709.00.00
W/2 NW NE, SECTION 19 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 5734 4950 FEET FROM S SECTION LINE
1650 FEET FROM E SECTION LINE

OPERATOR CULVER & GROUNDS OIL PROP
NAME & P O BOX 793
ADDRESS MCPHERSON KS 67460

LEASE NAME: NELSON #7-1
COUNTY: MCPHERSON
WELL TOTAL DEPTH: 3365' 109.36

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 158' **RECEIVED**

KANSAS CORPORATION COMMISSION
WICHITA, KS

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____ **NOV 19 1993**

PLUGGING CONTRACTOR: KELSO CASING PULLING
ADDRESS: CHASE KS LICENSE: 6050 CONSERVATION DIVISION
WICHITA, KS

COMPANY TO PLUG AT: HOUR: 8:30 DAY: 9 MONTH: 11 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: MANNEY

COMPANY NAME: KELSO PHONE: _____

WERE: SAND TO 3205' & 5 SX - 35 SX @ 850' - 35 SX @ 400' -
208' TO SURF

PLUGGING PROPOSAL RECEIVED BY: MIKE WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 12:30 DAY: 9 MONTH: 11 YEAR: 1993

ACTUAL PLUGGING REPORT:
SANDED BOTTOM TO 3205' & 5 SX COMMON - SHOT 5-1/2"
CSG OFF @ 2880' & PULLED TO 850' - PUMPED 35 SX -
PULLED TO 400' - PUMPED 35 SX - PULLED TO 208' - CIRC
CMT TO SURFACE

REMARKS: ALLIED #3787 60/40 4%

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE NOV 22 1993

INV. NO. 39272

15/
Jack Luthi (AGENT)