

2-010129

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

1-9

2:119.00.00

API NUMBER: 15-113-22,122

W/2 W/2 NW, SECTION 18 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 31534 3960 FEET FROM S SECTION LINE
OPERATOR SUSAN SWANSON 4950 FEET FROM E SECTION LINE
NAME & 972 PLUM AVE., R.R. 1, BOX 78
ADDRESS WINDOM, KS 67491
LEASE NAME: J. ALBERT #3
COUNTY: McPHERSON
WELL TOTAL DEPTH: 3429' 111.44
PIPE: _____
SURFACE CASING: 8 5/8" @ 252'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: QUALITY WELL SERVICE INC.
ADDRESS: 249 BETH DRIVE, STERLING, KS 67579 LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 9 MONTH: 1 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: STUART MILLER
COMPANY NAME: SUSAN SWANSON PHONE: (316) 257-3744
WERE: SAND TO 3250' AND TOP WITH 5 SACKS OF CEMENT. SHOOT PIPE OFF. PULL PIPE TO 800' AND SPOT 35 SACKS OF CEMENT. PULL PIPE TO 305' AND CIRCULATE CEMENT TO THE SURFACE.
5 1/2" CASING AT 3429'
PERFORATIONS FROM 3304-3314'

PLUGGING PROPOSAL RECEIVED BY: MICHAEL R. WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART () NONE (_____)
COMPLETED: HOUR: 15:30 DAY: 9 MONTH: 1 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED TO 3220' AND TOPPED WITH 5 SACKS OF CEMENT. SHOT PIPE OFF AT 2000'. PULLED PIPE TO 889' AND PUMPED 250# OF HULLS. PULLED PIPE TO 809' AND SPOTTED 35 SACKS OF CEMENT AND 100# HULLS. PULLED PIPE TO 412' AND CIRCULATED 100# HULLS. PULLED PIPE TO 339' AND CIRCULATED 130 SACKS OF CEMENT AND 100# HULLS TO THE SURFACE.

REMARKS: 60/40 POZ 4% GEL 550# HULLS UNITED #4875

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 24 1997

CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson
MICHAEL R. WILSON

INVOICED

DATE 1-24-97

INV. NO. 47441

MAR 14 1997 1-9

FORM CP-2/3
REV. 3/90