

RECEIVED
KANSAS CORPORATION COMMISSION

2-

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

DEC 16 1993
CONSERVATION DIVISION
WICHITA, KS

15.113.20743.00.01

API NUMBER: E-21,778

SW, SECTION 18 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 5734

1320

FEET FROM S SECTION LINE

4050

FEET FROM E SECTION LINE

OPERATOR CULVER & GROUNDS OIL PROP

NAME & P O BOX 793

ADDRESS MCPHERSON KS 67460-0793

LEASE NAME: SWANSON #1 SWD

COUNTY: MCPHERSON

WELL TOTAL DEPTH: 3361'

109.23

CONDUCTOR PIPE:

SURFACE CASING: 8-5/8" @ 773'/350 SX

ABANDONED OIL WELL GAS WELL INPUT WELL SWD X D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: KELSO CASING PULLING

ADDRESS: PO BOX 347 CHASE KS 67524

LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 13 MONTH: 12 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: MIKE KELSO

COMPANY NAME: KELSO CASING

PHONE: 316-938-2943

WERE: SAND TO 3244' & TOP W/5 SX - SHOOT OFF PIPE - PULL TO
825' & SPOT 35 SX CMT - PULL PIPE TO 250' & CIRC CMT
TO SURFACE

5-1/2" CSG @ 3294' - OPEN HOLE @ 3294'-3361'

PLUGGING PROPOSAL RECEIVED BY: RALPH TITTEL

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (X) NONE ()

COMPLETED: HOUR: 12:30 DAY: 13 MONTH: 12 YEAR: 1993

ACTUAL PLUGGING REPORT:

SANDED TO 3244' & TOPPED W/5 SX CMT - SHOT PIPE OFF
AT 2515' - PULLED PIPE TO 825' & SPOTTED 35 SX CMT -
PULLED PIPE TO 330' & CIRC 85 SX CMT TO SURF
RECOVERED 2515' OF 5-1/2" CSG

REMARKS: USED 60/40 POZ W/4% GEL - ALLIED #6029

I DID OBSERVE THIS PLUGGING.

INVOICED

DATE

12-29-93

INV. NO.

39579

12-13

MIKE WILSON

(AGENT)

FORM CP-2/3
REV. 3/90