

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

5-25

API NUMBER: 15-113-21,055.00.00

NE NW SW, SECTION 18 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 5734 2160 FEET FROM S SECTION LINE  
4290 FEET FROM E SECTION LINE

OPERATOR Culver Grounds Oil Prod.  
NAME & P.O.Box 793  
ADDRESS McPherson KS 67460

LEASE NAME: Swanson"B"Well#1

COUNTY: McPHERSON 109.68

WELL TOTAL DEPTH: 3375(3360)PB

CONDUCTOR PIPE: \_\_\_\_\_

SURFACE CASING: 8-5/8" @ 207'

ABANDONED OIL WELL  GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SLD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Kelso Casing Pulling Inc.  
ADDRESS: P.O.Box 347 Chase KS 67584-0347 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: 15:00 DAY: 25 MONTH: 5 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: Gene Grounds

COMPANY NAME: Culver & Grounds Oil Properties PHONE: 316-241-1179

WERE: Sand to 3240' & top with 5sx of cmt - Shot pipe off  
at 2320' - Pulled pipe to 775' & spotted 35sx cmt -  
Circ hole prior to cmtng. - Pulled pipe to 300' and  
circ 60sx cmt to surface.

PLUGGING PROPOSAL RECEIVED BY: Michael R. Wilson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART ( \_\_\_\_\_ ) NONE ( \_\_\_\_\_ )

COMPLETED: RECEIVED HOUR: 9:15 DAY: 25 MONTH: 5 YEAR: 1993

ACTUAL PLUGGING REPORT:

Sanded to 3240' & topped w/ 5sx cmt - Shot pipe off @  
2320' 1993 Pulled pipe to 775' & spotted 35sx cmt - circ  
hole prior to cmtng - pulled pipe to 300' & circ 60'  
sx cmt to surface. Recovered 2320' of 5-1/2" casing.

CONSERVATION DIVISION

REMARKS: Used 66/40 poz w/ 4%gel by Allied - Invoice #3136

**INVOICED**

I DID OBSERVE THIS PLUGGING.

DATE 6-2-93

Michael R. Wilson  
Michael R. Wilson (AGENT)

INV. NO. 32794