

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

1-3

API NUMBER: 15-113-21,161

N/2 N/2 NW, SECTION 18 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 31524
OPERATOR SUSAN SWANSON
NAME & R.R. 1, BOX 75
ADDRESS WINDOM, KS 67491

4950 FEET FROM S SECTION LINE
3960 FEET FROM E SECTION LINE
LEASE NAME: MARY ELLEN #2
COUNTY: McPHERSON
WELL TOTAL DEPTH: 3398' 110.43
PIPE: 5 1/2" @ 3396'- 100 SX
SURFACE CASING: 8 5/8" @ 224'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: QUALITY WELL SERVICE
ADDRESS: STERLING, KS LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 14:00 DAY: 2 MONTH: 1 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: RICHARD
COMPANY NAME: QUALITY WELL SERVICE PHONE: (316) 727-3410
WERE: SAND TO 3196'
CAP WITH 5 SACKS OF CEMENT
SHOOT PIPE FOR RECOVERY.

PLUGGING PROPOSAL RECEIVED BY: RALPH TITTEL

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 12:00 DAY: 3 MONTH: 1 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED TO 3196', CAPPED WITH 5 SACKS OF CEMENT. RECOVERED
2611' OF 5 1/2". THRU 5 1/2" SPOTTED 35 SACKS AT 825', 5 HULLS. PULLED TO 271',
CIRCULATED TO SURFACE. PLUG FELL TO 220', REFILLED TO SURFACE.

REMARKS: 60/40 POZ 4% GEL 170 SACKS ALLIED #1491
McPHERSON CONCRETE 7 YDS OF SLURRY MIX

INVOICED

DATE JAN 23 1997

INV. NO. 47436

DW MAR 14 1997 1-3

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 22 1997

CONSERVATION DIVISION
WICHITA, KS

I DID OBSERVE THIS PLUGGING.

Ralph Tittel
RALPH TITTEL