

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

1-2

API NUMBER: 15-113-21,100,00,00

SE SW NW, SECTION 18 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 31524
OPERATOR SUSAN SWANSON
NAME & R.R. 1, BOX 78
ADDRESS WINDOM, KS 67491

2900 FEET FROM S SECTION LINE
4290 FEET FROM E SECTION LINE
LEASE NAME: MARY ELLEN #1
COUNTY: MCPHERSON
WELL TOTAL DEPTH: 3400' 110.50
PIPE: _____
SURFACE CASING: 8 5/8" @ 206'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: QUALITY WELL SERVICE
ADDRESS: STERLING, KS LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 31 MONTH: 12 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: RICHARD
COMPANY NAME: QUALITY WELL SERVICE PHONE: (316) 727-3410
WERE: SAND TO 3214', CAP WITH 5 SACKS CEMENT
SHOOT PIPE FOR RECOVERY
35 SACKS AT 800'
CIRCULATE FROM 275' TO SURFACE

PLUGGING PROPOSAL RECEIVED BY: RALPH TITTEL

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { _____ } PART { } NONE { _____ }

COMPLETED: HOUR: 13:00 DAY: 2 MONTH: 1 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED TO 3214' AND CAPPED WITH 5 SACKS CEMENT. RECOVERED 2500' OF 5 1/2". THRU 5 1/2" SPOTTED 35 SACKS AT 800'. CIRCULATED FROM 275' TO SURFACE. PLUG FELL 70'. CAME BACK AND FILLED FROM 70' TO SURFACE.

REMARKS: 60/40 POZ 2% GEL 170 SACKS CEMENT, 8 SACKS HULLS
ALLIED #1490

INVOICED

DATE JAN 23 1997

INV. NO. 47435

MAR 14 1997 1-2

RECEIVED
KANSAS CORPORATION COMMISSION I DID OBSERVE THIS PLUGGING.

JAN 22 1997

Ralph Tittel
RALPH TITTEL

CONSERVATION DIVISION
WICHITA, KS