

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

12-26

API NUMBER: 15-113-21,052 '00.00

SW NW NW, SECTION 18 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 31534 4290 FEET FROM S SECTION LINE
OPERATOR SUSAN SWANSON 4950 FEET FROM E SECTION LINE
NAME & ADDRESS 972 PLUM AVENUE
R.R. 1, BOX 78
WINDOM, KS 67491
LEASE NAME: J. ALBERT #2
COUNTY: McPHERSON
WELL TOTAL DEPTH: 3375' 109.68
PIPE:
SURFACE CASING: 8 5/8" @ 229'

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: QUALITY WELL SERVICE
ADDRESS: 249 EAST BETH DRIVE, STERLING, KS 67579 LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 9:30 DAY: 26 MONTH: 12 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: STUART MILLER
COMPANY NAME: SUSAN SWANSON PHONE: (316) 257-3477
WERE: SAND TO 3250' AND TOP WITH 5 SACKS OF CEMENT. SHOOT PIPE OFF. PULL PIPE TO 750' AND SPOT 35 SACKS OF CEMENT. PULL PIPE TO 300' AND CIRCULATE CEMENT TO SURFACE.

PERFORATIONS AT 330-3307'
5 1/2" CASING AT 3374'

PLUGGING PROPOSAL RECEIVED BY: STUART MILLER

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (X) NONE ()

COMPLETED: HOUR: 13:30 DAY: 26 MONTH: 12 YEAR: 1996

ACTUAL PLUGGING REPORT: SANDED TO 3236' AND TOPPED WITH 5 SACKS OF CEMENT. SHOT PIPE OFF AT 2542'. PULLED PIPE TO 788' AND SPOTTED 35 SACKS OF CEMENT AND 200 LBS. OF HULLS. PULLED PIPE TO 315' AND CIRCULATED 120 SACKS OF CEMENT TO THE SURFACE. OPERATOR TOPPED WITH 3 YDS SLURRY MIX ON 1/3/97 (HAD FALLEN 225'). RECOVERED 2542' OF 5 1/2" CASING - 64 JTS.

REMARKS: 60/40 POZ 4% GEL ALLIED #1486

INVOICED

DATE JAN 23 1997

INV. NO. 47433

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 22 1997

I DID OBSERVE THIS PLUGGING.

Michael R. Wilson
MICHAEL R. WILSON

FORM CP-2/3
REV. 3/90

CONSERVATION DIVISION
WICHITA, KS

MAR 14 1997 12-26