

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2078  
Wichita, Kansas 67202

1-4

API NUMBER: 15-113-21,051.00.00

W/2 NW SW, SECTION 18 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 31524  
OPERATOR SUSAN SWANSON  
NAME & R.R. 1, BOX 78  
ADDRESS WINDOM, KS 67491

6620 1980 FEET FROM S SECTION LINE  
5020 4950 FEET FROM E SECTION LINE  
LEASE NAME: J. ALBERT #1  
COUNTY: McPHERSON  
WELL TOTAL DEPTH: 3370' 109.52  
PIPE: 5 1/2" @ 3360 - 150SX  
SURFACE CASING: 8 5/8" @ 200'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: QUALITY WELL SERVICE  
ADDRESS: STERLING, KS LICENSE: 31925

COMPANY TO PLUG AT: HOUR: 8:00 DAY: 4 MONTH: 1 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: RICHARD  
COMPANY NAME: QUALITY WELL SERVICE PHONE: (316) 727-3410  
WERE: SAND TO 3164'  
CAP WITH 5 SACKS OF CEMENT  
SHOOT PIPE FOR RECOVERY.

PLUGGING PROPOSAL RECEIVED BY: RALPH TITTEL

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL {  } PART {  } NONE {  }

COMPLETED: HOUR: 11:00 DAY: 4 MONTH: 1 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED TO 3164', CAPPED WITH 5 SACKS OF CEMENT. RECOVERED 2430' OF 5 1/2". THRU 5 1/2" SPOTTED 35 SACKS AT 797'. PULLED TO 280', CIRCULATED TO SURFACE. PLUG FELL TO 180', REFILLED WITH 80 SACKS OF CEMENT.

REMARKS: 60/40 POZ 4% GEL 250 SACKS CEMENT, 8 HULLS UNITED #1496

RECEIVED  
KANSAS CORPORATION COMMISSION

I  DID OBSERVE THIS PLUGGING.

INVOICED

JAN 22 1997

Ralph Tittel  
RALPH TITTEL

DATE JAN 23 1997

CONSERVATION DIVISION  
WICHITA, KS

FORM CP-2/3  
REV. 3/90

INV. NO. 47432

MAR 14 1997 1-4