

4-28

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

API NUMBER: 15-113-21,045.00.00

CS/2SESW, SECTION 18 TOWNSHIP 20 RANGE 5W

OPERATOR LICENSE # 5734 330 FEET FROM S SECTION LINE

3300 FEET FROM E SECTION LINE

OPERATOR Culver & Grounds Oil Prop.

NAME & P.O.Box 793

ADDRESS McPherson KS 67460-0793

LEASE NAME: Swanson "A" #1 (27)

COUNTY: McPherson 109.46

WELL TOTAL DEPTH: 3368'

PIPE: 5-1/2" @ 3368' / 75sx

SURFACE CASING: 8-5/8" @ 210'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SMD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Kelso Casing Pulling Inc.

ADDRESS: P.O. Box 347 Chase KS 67524 LICENSE: 6050

COMPANY TO PLUG AT: HOUR: pm DAY: 28 MONTH: 4 YR: 1993

PLUGGING PROPOSAL RECEIVED FROM: Mike Kelso

COMPANY NAME: Kelso Casing Pulling Inc. PHONE: 316-938-2943

WERE: Sand to 3200'/cap w/ 5sx cmt - Shoot pipe - Pull csq to 775' - 35sx cmt - pull csq to 300' - circ cmt to surface

PLUGGING PROPOSAL RECEIVED BY: Dist #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 1:30p DAY: 28 MONTH: 4 YEAR: 1993

ACTUAL PLUGGING REPORT:

Sanded to 3200'/capped w/ 5sx cmt - Pipe was parted -

Pulled csq to 800' - tried to load hole - 35sx cmt -

RECEIVED  
Loaded csq to 350' - loaded hole & circ cmt (120sx) -

3284' - 3251' - Rec 2228' -

REMARKS: Added Cmt #5973 60/40 poz 4% gel

INVOICED

DATE 6-4-93  
WV. NO. 37823  
4-28

Phil Worley  
R. Phil Worley (AGENT)