

15.113.05012.00.00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 20 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Braden-Deem, Inc.
Complete Address: 210 One-Twenty Bldg., Wichita, Kansas 67202
Lease Name Lindquist Well No. 1
Location CWL NE SE Sec. 19 Twp. 20 Rge. 5 (E) X (W) X
County Mc Pherson Total Depth 3357'
Abandoned Oil Well Gas Well Input Well SWD Well X D & A
Other well as hereafter indicated:
Plugging Contractor: Operator

Address: License No. 580
Operation Completed: Hour 4:30 PM Day 18 Month December Year 1968

The Above well was plugged as follows:

Hole filled with sand to 3320' and cemented with 5 sacks cement.
Hole filled with mud to 180'. Rock bridge set from 180' to 170' and hole cemented
with 25 sacks cement. Hole filled with mud to 40'. Rock bridge set from 40' to 30'
and hole cemented to base of cellar with 10 sacks cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/23/68
INV. NO. 9073-u

Signed *W. J. Loman*
Well Plugging Supervisor