

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock

██████████
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

RECEIVED
 STATE CORPORATION COMMISSION
 DEC 22 1969
 CONSERVATION DIVISION
 Wichita, Kansas

Operator's Full Name F.G.HollComplete Address: 6427 E. Kellogg. Wichita, Kansas 67207Lease Name Nyquist Well No. # 1Location C N/2 NE NW Sec. 19 Twp. 20 Rge. 5 W (W)County McPherson Total Depth 3395'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Pipe Pullers Inc.,Address: Ellinwood, Kansas License No. # 462Operation Completed: Hour 3 PM Day 19 Month 12 Year 69

The Above well was plugged as follows:

8 5/8"-190'-Circulated w/cement. 5 1/2"-3297'-Circulated w/cement.Plug back w/sand 3395' to 3355'. Plug back w/cement 3355' to 3345'.Plug back w/sand 3345' to 3290'. 5 Sax.cement 3290' to 3250'.Mud 3250' to 210'. Bridge 210' to 200'. 7 Sax.cement 200' to 130'.Mud 130' to 40'. Bridge 40' to 30'. 4 Sax.cement 30' to 0.No Pipe Pulled.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Hugh Scott

Well Plugging Supervisor

DATE 12/23/69INV. NO. 1104-a